6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chief Electrical Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of detailed quantities for constructing a Central Stores of Electrical Department, at S. M. Ry. Yard, Bangalore.

No.	Items of work	Per	Quantity
1	Earthwork excavation	C. yd.	230
2	Earthwork filling in basement	"	1,167
3	Stone in mortar foundation and basement	C. ft.	12,678
4	Stone in mortar superstructure	"	14,497
5	Cut stone arch work	"	82
6	Stone slabs, 6" thick	S. ft.	1,643
7	Cement pointing	Sqr.	190·5
8	Cuddappah slab flooring, 2" thick on 3" concrete and cement pointing	"	152·50
9	Gravel flooring, 6" thick	"	67·54
10	Corrugated iron roofing, complete	"	105·92
11	Verandah pillars, (pole sockets, 8" diameter)	No.	16
12	Main pillars, (pole sockets filled with cement concrete)	"	24
13	W. I. trusses for 30 ft. span	"	12
14	Carriage, hoisting and fixing charges for above	"	12
15	W. I. work	Cwt.	174·78
16	T. W. work with wood oiling	C. ft.	37·78
17	T. W. glazed windows with iron bars, (1½")	"	456
18	T. W. circular windows, glazed	"	25
19	Painting with 3 coats of silicate paint	Sq.	23·00
20	T. W. pannelled doors, 2" thick	S. ft.	250

S. G. FORBES,
Chief Electrical Engineer to the Government of Mysore.

BANGALORE DIVISION.

Abstract Notification.

Attention is invited to the notification published in Part IV of the *Mysore Gazette* dated 1st August 1918, calling for tenders for "Special Repairs of Roads in Cubbon Park," Bangalore.

Abstract Notification dated 29th July—1st August 1918.

Attention is invited to the notification calling for tenders for constructing an additional block adjacent to the District Office building at Bangalore, published in *Mysore Gazette*, dated the 8th August 1918.

Notification dated 9th August 1918.

Sealed tenders will be received for the supply of coir matting for the verandahs in the Public Offices, Cubbon Park, Bangalore, up to 4 P.M., on Monday the 19th August 1918. The matting required is for a length of 435 running feet approximately for a width of 6 feet. The matting to be in two pieces of 3 feet width stitched together.

Tenders should be accompanied by earnest money of Rs. 50 in currency or Government Promissory Notes. The supply should be finished within 8 days of the acceptance of the tender.

Dated 1—7th August 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer Bangalore Division, up to 4 P.M. on 28th August 1918, for constructing an additional Laboratory in the compound of Lambourne House at Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 4 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing an additional Laboratory in the compound of Lambourne House at Bangalore in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates tendered must be specific:—Tenders with vague quotations, such as "as per market rates," will not be accepted.

Constructing an additional Laboratory in the compound of Lambourne House at Bangalore.

Items of work.	Per	Rate	Quantity	Cost
		Rs. a. p.		Rs.
Earthwork excavation and filling basement	C. yd.	...	186	
Chunam concrete	C. ft.	...	1,377	
Stone in chunam foundation and basement including bond stones at 6' apart.	"	...	5,001	
Burnt stone slabs R. D. 6" thick	S. ft.	...	1,574	
Burnt brick in mortar	C. ft.	...	6,182	
Archwork with wire cut bricks in chunam	"	...	78	
Pillars of wire cut bricks in chunam (1½'×1½') with bearing slab base, capital including painting and colourwashing.	No.	...	16	
Teakwood panelled doors with brass fittings highly finished including iron clamps.	S. ft.	...	198	
Teakwood sash windows with brass fittings	"	...	84	
Do glazed windows, complete	"	...	392	
Do rectangular ventilators	"	...	120	
Do circular do	"	...	25	
Steel trusses including hoisting, complete	No.	...	4	
Bed slabs below trusses including bolts, etc., complete ...	"	...	8	
Teakwood wrought and put up with wood oiling	C. ft.	...	217·27	
Pukka terrace roof	Sq.	...	0·75	
Roofing with 1st class Mangalore tiles on teak reepers, chunam borders, etc.	"	...	12·34	
Roofing with 1st class Mangalore tiles on teak reepers with ceiling tiles, chunam borders, etc.	Sq.	...	27·72	
Ridge tiles set in mortar	R. ft.	...	115	
Valley gutters over ½" plank 3' wide zinc sheet, complete, including cement plastering and edges, etc.	"	...	15	
Teakwood ornamental eave board 1' deep with painting	"	...	371	
Cornice 9" deep all round verandah room	"	...	28	
Teakwood turned finials	No.	...	2	
Do down pendants	"	...	11	
Parapet wall 3' high	R. ft.	...	24	
Chunam plastering	Sq.	...	93·63	
White and colourwashing	"	...	43·43	
Calcarium washing	"	...	48·54	
Dado painting with calcarium	R. ft.	...	280	
Silicate painting	Sq.	...	13·48	
Flooring with Cuddapah slabs over 3" concrete including cement pointing.	"	...	11·52	
Flooring with acid proof tiles on 3" concrete and cement pointing ...	"	...	4·80	
Flooring with Mangalore square tiles	"	...	7·00	
Constructing flights of steps opening a door way to museum and constructing a flue with fire-bricks, casing in fire clay.	L. S. Rs.	...	...	200
Chunam pointing to basement	Sq.	...	9·00	
Fixing a water basin in verandah room and drainage arrangement	L. S. Rs.	...	...	200
Rolled steel joists 4½"×1½" seet at 6½ lbs. per R. ft. ...	Cwts.	...	4·17	
Providing and fixing an iron water tank 6' Dr.×3' height with a light cover of corrugated iron on S. M. Rails placed on bed slabs (1½'×1½'×6") etc.	L. S. Rs.	...	...	400

C. VIJAYARANGAM NAIDU,
Executive Engineer.

KOLAR DIVISION.

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part IV, pages 698—699, calling for tenders for restoring Suranahalli tank, Regd. No. 174 of Bowringpet Taluk.

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part IV, page 699, calling for tenders for constructing a compound wall around the special lock-up at Champion Reefs, Kolar Gold Fields.

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part IV, page 697, calling for tenders for constructing the A.-V. School at Bagepalli.

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette*,